



CMS Project Status and Issues

- **Magnet**
- **Schedule/Milestones**
- **Funding Risks**
- **Contingency Plans**
- **Tracker Issues**
- **Software/Computing Issues**

DOE/NSF Review
FNAL
19 August 1999

M. Della Negra
CMS Spokesperson



Magnet Cost

	Cost V9 (MCHF)	Cost V10 (MCHF)	Committed (MCHF)	Not Comm. (MCHF)
Barrel/Vac. Tank	31.2	31.4	27.0	4.4
End-Caps	21.2	15.9	10.4	5.5
Coil	64.7	68.2	31.5	36.7
Installation	4.8	6.3	0.0	6.3
TOTAL	121.9	121.8	68.9	52.9


The tender for the winding of the coil (15 MCHF) has been launched in May by INFN. Answers are expected by 10th September. This is a strategic contract as the winding operation is on the critical path.

The magnet project is on budget and on schedule. However the situation will be really understood only after the contract for the winding has been awarded (70% of total magnet cost committed).



Magnet Payment Profile (1)


Cost Estimate 10.06






Magnet Payment Profile (2)


Cost Estimate 10.06



Magnet Barrel Yoke




Ferris Wheel Design





Ferris Wheel at DWE (1)






Ferris Wheel at DWE (2)






Ferris Wheel at DWE (3)





Summary Schedule (1)


CMS Summary Schedule v 1.0 9th June 1999 (preliminary)





Summary Schedule (2)

CMS Summary Schedule v 1.0 9th June 1999 (preliminary)





Milestones (1)

CERN/LHCC 99-26

Milestones CMS Milestones - version 2.0 31'st July 1999

Level 1 Milestones

Surface Hall (SX5) ready	01/00
Underground Hall (UX5) Ready	01/03
Submit Trigger TDR	11/00
Submit DAQ TDR	12/01
End Assembly of Barrel Yoke	06/01
End Assembly of Endcap Yoke	01/02
End Assembly of Coil	02/03
Slide Coil into Vac-tank	04/03
End Assembly of HB in SX5	07/02
End Assembly of HE (on YE) in SX5	05/02
End Trial Insertion of HB in Vac Tank	07/03
End Trial Mounting of EB Super Module on HB	08/03
Start Cool-down of Coil	08/03
Close Yoke, and Start Magnet Test in SX5	09/03
Start Lowering Magnet Parts	01/04

etc. (24 L1 Milestones, 164 L2 Milestones, 216 L3 Milestones)



Milestones (2)

Milestone reporting:

Level 1 : in writing to CMS Steering Committee & LHCC

Level 2 : in writing to CMS Steering Committee & LHCC


Level 3 : verbally to CMS Steering Committee and
to LHCC referees by CMS Technical Coordination

Note: US CMS Milestones L1 and L2 are a subset of the CMS
Milestones



Point 5 Design

POINT 5 ORGANISATION CHANTIER PHASE I




HERVE A
MICHALO JF
LE 28 NOVEMBRE 1995
MISE A JOUR LE 30 - JUILLET - 1996
MISE A JOUR LE 24 SEPTEMBRE 1996
MISE A JOUR LE 6 DECEMBRE 1995

MOD LE 5 - FEV - 1998 SUPPRESSION DU SRL



Point 5 August 1999





Funding Risks

Magnet	3.1 MCHF	Tracker	1.0 MCHF
Barrel Yoke Contract (R)	1.4 MCHF	FWD MSGCs (R)	1.0 MCHF
Dump Resistor (R)	0.3 MCHF	ECAL	2.7 MCHF
Common Fund (K)	1.4 MCHF	EE Mechanics (R)	1.0 MCHF
Infrastructure	2.1 MCHF	EE VPTs (R)	0.8 MCHF
Racks (R)	0.4 MCHF	Preshower (G)	0.9 MCHF
Riser system for HF (R)	0.3 MCHF	Muons	3.5 MCHF
Shielding and table for HF (R)	1.4 MCHF	FWD RPCs, 3 stations (K)	2.0 MCHF
HCAL	3.1 MCHF	ME1/1 electronics (R)	1.5 MCHF
HE Brass (550 tons) (R)	1.6 MCHF	TriDAS	1.4 MCHF
Mechanics for HF (R)	1.1 MCHF	DAQ (G)	0.9 MCHF
HF Optics (H)	0.4 MCHF	RPC Trig (K)	0.5 MCHF

Total Funding Risk : 16.9 MCHF

(Russia 10.8 MCHF, Korea 3.9 MCHF,
Hungary 0.4 MCHF, Greece 1.8 MCHF)



Funding Risks: A Common Problem

Extract from a letter from the Spokesperson to D. Green and E. Temple:

The Collaboration has decided to consider the funding risks as a common problem, i.e. manage as common projects.

The total shortfall has been estimated to be about 17 MCHF in deliverable value.

In the US accounting system this translates to about 30 MUSD of risk in total project cost.

The US share of this risk is 20%, i.e. some 6 MUSD.

Time critical components requiring the immediate help from the Collaboration have been identified.

Immediate help from US_CMS:

- 1) HF engineering design to be regrouped in FNAL.
- 2) Procurement of 550 tons of brass plates for HE (1.6 MCHF).

Help from US_CMS to be decided by the end of the year:

- 3) HF mechanics and Optics (1.5 MCHF)
- 4) HF shielding and Table (1.4 MCHF)
- 5) ME1/1 electronics (1-1.5 MCHF)

CMS management will work to minimize the impact of common problems but we expect that some permanent redistribution of responsibility will be necessary. In addition there is some uncertainty in the cost of the tracker as the design will only be frozen at the end of the year.

It was therefore decided to define by the end of 1999 a new baseline CMS Detector, which could be guaranteed to be ready in 2005, within the available resources.



Roadmap for Decisions (1)

1999

- Jun YB Iron Blocks (1.4 MCHF) (CERN to CF)
- Jun Decision on transfer of full HF engineering design to FNAL
- Jun Dump Resistor (0.3 MCHF) (CERN to CF)
- July HE Brass (550 tons 1.6 MCHF) (US)

Decide up to here

- Dec Freeze baseline Tracker. Revise Baseline CMS detector.
- Dec Finalize Funding Plan for HF
Mechanics and Optics (1.5M\$ → 1.5 MCHF) (US)
Table and Shielding for HF (1.4 MCHF) (US)
- Dec ME1/1 electronics (Chips and components, 1-1.5 MCHF, US)

2000...



Roadmap for Decisions (2)

2000

- Feb Tracker MSGCs (sensor EDR- Feb: 1.0 MCHF – absorb in re-optimization Tracker)
- Jun Forward RPCs (3 stations + ME1/1) (procure 1 MCHF of RPC material? and send to Pakistan for assembly and test)
- Jun ECAL: After ECAL Endcap EDR in June procure alveolar structures (1.0 MCHF) and VPTs (0.8 MCHF) using ECAL funds (international competitive tendering should have been organised in advance, 1999?)

2001

- Dec Racks (0.4 MCHF) (covered by CERN)

2003

DAQ (0.9 MCHF) Greece

????

Preshower (0.9 MCHF) Greece
RPC Trigger (0.5 MCHF) Korea
CF shortfall (Korea 1.4 MCHF)



Tracker Issues

	Phase II Si + MSGC (MCHF)	Funding (MCHF)	Phase I Si + MSGC (MCHF)	Baseline 1 Si + MSGC (MCHF)	Baseline 2 All Silicon (MCHF)
Pixels	8.2	8.0	8.2	8.2	8.2
Inner (Si)	30.5	24.7	25.3	25.0	25.0
Outer (MSGC or Si)	42.6	34.3	34.4	36.0	39.1
Gen. Mechanics	6.1	5.9	6.1	6.1	6.1
TOTALS	87.4	72.9	74.0	75.3	78.4

Phase II: TDR Design full luminosity, Electronics rad hard CMOS (2.8 CHF/Ch.)

Phase I: TDR Design, staging scenario.

Avoid Staging scenario: Reduce #channels by 10%, Submicron Electronics (2 CHF/Ch.)

Baseline 1: Inner 5 Silicon, outer 6 MSGC layers

Baseline 2: Inner 5 Silicon, outer 5 Silicon layers (All Silicon)

Decision between Baseline 1 and 2 in December 1999 based on feasibility, schedule, cost and performance.

MSGC: Robustness test at PSI in November

Silicon: Large (11 cm), long (16.5 cm), thick (400 μm) detectors (6" technology)



Expected Performance B2 vs B1

Tracking Performance:

- Less points (5 vs 6)
- Less double-sided layers (2 vs 3)
- Similar resolution (40 μm)
- Same momentum Resolution
- Same impact parameter/b-tagging performance
- Pattern Recognition expected to be the same
- Smaller dependence on the angle of the tracks

Material Budget:

Expected to be equal or lower

ALL THIS TO BE VALIDATED BY SIMULATION



Software/Computing Issues

High Level Triggers:

- After a hardware Level-1 all further event selection occurs in a farm of processors.
- well engineered, reliable and efficient software is needed, must be ready in 2005.
- Distinction between online and offline software should be minimal.
- CMS Decision: Stop Fortran developments, switch to C++ and OO.
- Second version of offline reconstruction in OO released June 1999 (ORCA-2)..
- Physics Reconstruction and Selection sub-project formed in April.

Initial goal: tackle Level-2, 3, ... and provide required input for DAQ TDR (end 2001).

Led by P. Spiccas (MIT/CERN) + 4 Conveners + Sw/Comp rep.

e/ γ : C. Seez, jets/ E_t^{miss} : S. Eno (Maryland), μ : U. Gasparini, b/ τ : A. Caner

Offline Computing (Model):

- Centre at CERN (storage of raw data, first reconstruction pass)
- 'Regional Centres' to reconstruct, analyse, simulate, store, with network access and a capability of $\approx 20\%$ of centre at CERN
- Address these issues in 'MONARC' LCB Common Project at CERN
- CERN Director of Research has launched a Review of LHC Computing to report back by end 2000. Review political, financial and technical implications.